



The  
Caisson  
Company

— A POLE BASE COMPANY

**Light Pole Bases**  
**Drilling Services**

**Bollards & Sign Bases**

## Sample Proposal

Tuesday, July 24, 2018

Company Name  
Company Address

RE: Job Name  
Job Address

ATTN: Contact Name

Thank you for the opportunity to provide our proposal to Mobilize your jobsite to Drill, Install Supplied Bollard, and Place Concrete for (2) Bollards as follows:

A Quantity of:

**(2) Protective Bollards @ 8' Length** installed in a 30" Diameter Hole drilled to a depth of 4' Below Grade, Bollard supplied by Reliance Metal Center, set and poured to a height of 4' above grade with concrete square cap domed finish. Concrete will be poured and sloped away from bollard for drainage with no Sono Tube Forming assumed to be needed. 4000 P.S.I. Commercial Grade Concrete will be used for construction.

Price Per Unit Installation	\$ 557.38
Short Load Concrete Fee	\$ 85.00
Small Quantity Mobilization	\$ 300.00
<b>Total Price for Installation</b>	<b>\$ 1,499.76</b>

Clean up area upon completion and place rubbish in onsite dumpster provided by others. Spread excess dirt on site. Project has been bid with consideration of (1) Mobilization. A mobilization can be defined as (1) Day to Drill, Set, & Pour Bollard. Final Steel Prep, Priming, Painting, Bollards Materials and reflective tape by others after installation.

The Caisson Company requests that at least (1) 5' offset be laid out to insure proper location and elevation.

EXCLUSIONS: *Bollard Materials, Steel Prep, Priming, Painting, reflective tape supply/install, Private Locates, Construction of Concrete Washout Pit, Layout of bollard bases, rock excavation, dewatering of excavation, permits, testing, and inspections.*

**Total Price for (2) Bollards Installed** **\$1,499.76**

Terms: Payment upon completion or per contract agreement

Respectfully submitted,  
Haley Dechant  
Estimator

Signature of Acceptance

Printed Name

Date

Phone (719) 597-5674  
Fax (719) 573-4343

7917 Red Granite Loop Suite 110  
Colorado Springs, CO 80939