



The
Caisson
Company

— A POLE BASE COMPANY

Light Pole Bases Drilling Services

Bollards & Sign Bases

MUSCO Sample Proposal

Wednesday, August 22, 2018

ABC Company
ABC Drive
Colorado Springs, CO 80916

RE: Football Stadium
Colorado Springs, CO 80939

ATTN: Estimating

Thank you for the opportunity to provide our proposal to Mobilize your jobsite and Drill, supply & install steel, & Provide and Place Concrete for (6) Piers as follows:

(2) 30" Diameter, 16' Below Grade and 0" Above Grade and install Supplied Musco Lighting Precast Concrete Piers to Specifications supplied by ABC Company. 4000 P.S.I. Commercial Grade Concrete will be used for construction. Concrete will be left down approximately 2.5' for conduit access. Adequate access with equipment will be required. No soils report provided for bidding.

Contact For Pricing

(4) 30" Diameter, 18' Below Grade and 0" Above Grade and install Supplied Musco Lighting Precast Concrete Piers to Specifications supplied by ABC Company. 4000 P.S.I. Commercial Grade Concrete will be used for construction. Concrete will be left down approximately 2.5' for conduit access. Adequate access with equipment will be required. No soils report provided for bidding.

Contact For Pricing

(10,000lb Extended Reach Forklift, Concrete Piers, Tapered Level, and Picking Bar have been supplied by ABC Company.) Concrete will be left 30" Below Grade for electrical access and installation per drawings on Musco type Lights. 2.5' Backfill of Dirt around Pole by others. Clean up area upon completion and place rubbish in onsite dumpster provided by others. If ramps are needed to be constructed, they will be billed at an additional hourly charge of \$145.00/hr using dirt from holes being dug and being cleaned up and spread after holes are drilled. Landscape protection and repairs by others. Fence removal and repair for drill rig access by others as needed.

The Caisson Company requests that (2) 5' offset be laid out to insure proper location and elevation.

EXCLUSIONS: *Track & Field Protection & Repairs, Hole Protection, Landscape Protection, Landscape Repairs, Asphalt Saw cutting or removal, Concrete Pump, 10,000lbs extended reach forklift, Layout of pole bases, rock excavation, dewatering of excavation, permits, testing, Light poles, Electrical conduit installation and wiring, grouting under and around pole base cover, Rubbed Finish, Grounding Wire or Ground Wire installation, Light Pole Erection or Placement, Traffic Control, Concrete Washout Construction, Eco Pan, and inspections,*

Based on Normal Drilling Conditions.

Based on Completion Within (3.5) Hours for drill rig. Crew will remain to set and pour Musco piers.

If Additional Time is Needed, Add \$350.00 / Each Additional Hour Onsite.

If Rock Auger or Core Barrel is Needed, Add \$350.00 / Hour.

Phone (719) 597-5674

Fax (719) 573-4343

7917 Red Granite Loop Suite 110

Colorado Springs, CO 80939